S-377
John Wesley Methodist Church
Mount Vernon vicinity
public worship

1887

The John Wesley United Methodist Church, erected in 1887, is a prominent Gothic Revival frame church erected on the north side of Mount Vernon Road. In contrast to many other tee or ell-plan churches, John Wesley Church was designed with an axial plan and a corner bell tower. Instead of pointed arch openings the windows are finished with round arches. Surrounding the church on three sides is a nineteenth and twentieth-century cemetry that is bordered by a modern linked chain hung between brick piers. The church hall stands on the south side of Mount Vernon Road.

Survey No. \$-377

Maryland Historical Trust State Historic Sites Inventory Form

Magi No. 2003775608 DOE __yes __no

4 Now		_		
1. Nam	le (indicate pr	eferred name)		
historic John	n Wesley Methodist (Church		
and/or common				
2. Loca	ation			
street & number	Md. 362, Mt. Vern	on Road		
			_	not for publication
city, town Mt.		_X_ vicinity of	congressional district	First
state Maryl		county S	omerst	
3. Clas	sification			
Category district building(s) structure site object	Ownership public public private both Public Acquisition in process being considered not applicable	Status x occupied unoccupied work in progress Accessible x yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation other:
4. Own	er of Prope	rty (give names an	d mailing address	es of <u>all</u> owners)
name Trust	ees of John Wesley	United Methodist Ch	ırch	
street & number			telephone	no.:
city, town Mt .	Vernon	state	and zip code Md.	
		al Descriptio		
courtnouse, regis	stry of deeds, etc. Somers	et Clerk of Court		liber
street & number	Somerset County Co	urthouse		folio
city, town Pri	ncess Anne		state	Md. 21853
6. Repr	resentation	in Existing	Historical Sur	veys
title				
date			federal sta	ate county local
epository for su	rvey records			
city, town			state	

7. Description

Survey No. s-377

excellent deteriorated unalteredX_ original site _x good ruinsx_ altered moved date of move fair unexposed	x_ good	ruins		•	_		
--	---------	-------	--	---	---	--	--

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

John Wesley United Methodist Church description

John Wesley United Methodist Church is located on the north side of MD 362, 5.7 miles west of Princess Anne. Somerset County, Maryland. The large, single story frame church faces south with the principal gable oriented on a north/south axis. The church hall stands on the south side of the road.

Built in 1887, this large single-story gable frame church is supported by a minimal brick foundation, and it is uniformly sheathed with aluminum siding. The steeply pitched asphalt shingle roof has extended eaves. Rising on the southwest corner of the building is a three-story bell tower. Surrounding the church on three sides is the church cemetery.

The double leaf front door is topped by a two-light transom, and the entrance itself is protected by a shed roof that stretches between the tower and a one-bay gabled section that fills the right (east) bay. The upper gable of the sanctuary is pierced by a round, colored glass windows, whereas the third floor is pierced by a large louvered bellfry. The pyramidal roofed spire is marked on each side by a gabled vent. The single-story gable roofed section to the east of the entrance is lighted on its south side by a round arched sash window. Fixed in the southwest corner of the foundation is a marble date plaque engraved, "John Wesley M.E. Church, A.D. 1887."

The east and west sides of the rectangular sanctuary are divided into four bays with each bay defined by a round arched colored glass window.

The north (back) side of the church is extended by a shorter single-story altar supported by raised foundation. The brick foundation wall is pierced by three-light windows. Defining each side of the apse is a paired round arched window. Rising against the north wall is an exterior brick stack.

The interior was not open on the initial visit.

Surrounding the church on three sides is a nineteenth and twentieth-century graveyard that is bordered by a modern chain fence linked between brick piers. The church hall is a single-story frame structure erected on the south side of the road.

0. 31	giiiicance	Survey No.	S-377
Period	1499	law literature military music t philosophy politics/government	x religion science sculpture social/ humanitarian theater transportation other (specify)
Specific d	ates 1887 Builder/Architect		
A	Applicable Criteria: _A _B _C _D and/or Applicable Exception: _A _B _C _D Level of Significance:nationalstate		
support.	both a summary paragraph of significance and a	a general statement o	f history and

The John Wesley United Methodist Church, built in 1887, is a prominent structure which was built directly on the main road to Mount Vernon. In contrast to many other tee or ell plan churches, John Wesley of Mount Vernon was erected with an axial plan and a corner bell tower. Instead of pointed Gothic windows the openings were built with round arches. The John Wesley Methodist church is one of the older Methodist congregations in the immediate vicinity of Mount Vernon.

10. Geographi	cal Data		
Acreage of nominated property	uplete UTM refere	ences	Quadrangle scale 1:24000
Zone Easting N	orthing	B Zone E	Easting Northing
C		□	
Verbal boundary description	and justification		
List all states and counties	or properties overla	apping state or cou	nty boundaries
state	code	county	code
state	code	county	code
11. Form Prep	ared By		
name/title			
organization		date	e
street & number		tele	phone
city or town		stat	te

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust


Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

WAR DEPARTMENT CORPS OF ENGINEERS, U. S. ARMY





John Wesley Methodist Church Princess Anne, Somerset Co. Md. Southwest Elevation 3/86, Paul Touart, Photographer Neg/Md. Historical Trust S - 377



John Wesley Methodist Church Princess Anne, Somerset Co. Md. West Elevation 3/86, Paul Touart, Photographer Neg/Md. Historical Trust S - 377



John Wesley Methodist Church S-377
Princess Anne, Somerset County, Md.
South Elevation
4/86,Paul Touart, Photographer
Neg/Md. Historical Trust